



Moyglare Rd, Kilcock, Co Meath
Ph: 01 9033092

Email: info@streamlineenvironmental.ie
Web: www.streamlineseptictanks.ie

This drawing is Copyright to Ryan Civil Contracting t/a Sepcon.

Notes:

1. Do not scale from this drawing. Only for illustration purposes.
2. Professional installation: Sepcon provide a complete turn-key installation service to homebuilders and issue the relevant ancillary compliance certificates upon completion in accordance with the building regulations part H.
3. Observe all safety regulations in regard to excavation and lifting requirements. Never leave opening uncovered or unattended at any time.
4. The maximum hydraulic loading per module should never exceed a 150 liter dose in a 8 hour period. Each module is designed to cater for an overall daily hydraulic loading of 450 liters in total.
5. If used in conjunction with a system other than a Streamline BAF, you should confirm that the outlet dose volume does not exceed the requirements stated in note 4.

Project Name: StreamClear Tertiary Treatment Pod

Drawing Title: PE6 / 900Litres Per Day

Address:

Project No:

Client Ref:

Date:

Scale: N.T.S

Rev. no:

Dwg No.